BRUHATH BANGALORE MAHANAGARA PALIKE

Executive Engineer, SWD, R.R.Nagara Zone Division

Tender Notification No: EE/SWD/RR-N/TEND/03/2018-19, Dated:27-02-2019.

SCHEDULE-B

Name of Work: :Construction of U shape Drain to SWD at across Beside St Clarence School in ward no.16 Jalahalli of RR nagar Zone

Name Of The Contractor : Sri.B.G.Srinivas

It.No.	Quantity	Description / Specification code	Unit	Approved Rates (in Rs.)	
				In Figures	In Words
1	2	3	4	5	6
1	2.16	Dismantling of Existing Structures like Culverts,Bridges,Retaining Walls and other structures comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding where ever necessary,sorting the dismantled material,disposal of unserviceable material and stacking the seviceable material with all lifts complete as per specifications. by Mechanical means prestressed/ reinforced cement concrete grade M15 & M20.	Cum	413.00	Rupees Four Hundred Thirteen Only
2	32.40	Dismantling of Existing Structures like Culverts,Bridges,Retaining Walls and other structures comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding where ever necessary,sorting the dismantled material,disposal of unserviceable material and stacking the seviceable material with all lifts complete as per specifications.Rubble stone masonry in cement mortar	Cum	372.00	Rupees Three Hundred Seventy Two Only
3	19.44	Diversion of Water course by providing coffer dams or bunds or islands as may be necessary for piers and abutments, foundations, bailing out or pumping water during exavation and until completion etc., complete 1.5m depth below LWL	Cum	319.00	Rupees Three Hundred Nineteen Only

Srinivasa B G.
Contractor

Executive Engineer
SWD, R.R.Nagara Zone

Scanned by CamScanner

4	54.00	Earth work in Excavation for foundation of structures as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material complete as per MORTH specification No.304 V. in Marshy soil upto 3m depth By mechanical means	Cum	156.00	Rupees One Hundred Fifty Six Only
5	108.00	Earth work in Excavation for foundation of structures as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material complete as per MORTH specification No.304 B. in Ordinary soil upto 3m depth By mechanical means	Cum	54.00	Rupees Fifty Four Only
6	16.20	Providing and Filling in foundation with granite trap broken metal with available boulders,and providing with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications.specification. No. KBS	Cum	1527.00	Rupees One Thousand Five Hundred Twenty Seven Only
7	5.40	Providing and filling in foundation with granite/trap broken metal of 100 MM and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour charges and with all lead and lift etc complete as per specification and the direction of the Engineer in charge	Cum	2000.00	Rupees Two Thousand Only
8	10.80	Plain Cement Concrete M15 with OPC cement @ 240 kgs, with 40mm and down size graded granite metal coarse aggregates @0.84 cum and fine aggregates @ 0.56cum, in open foundation complete as per Drawing and Technical Specification MORTH Specification No.1500, 1700 &	Cum	4800.00	Rupees Four Thousand Eight Hundred Only
9	26.64	Plain/reinforcement Cement Concrete design mix M25 with OPC cement @340 kgs. with 20mm and down size graded granite metal coarse aggregates @ 0.70cum and fine aggregates @0.47cum with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, open foundation complete as per Drawing and Technical Specification with Batching plant, transit mixer and concrete pump. MORTH Specification No. 1500, 1700 & 2100	Cum	5100.00	Rupees Five Thousand One Hundred Only
10	26.68	Plain/reinforcement Cement Concrete design mix M25 sub structure with OPC cement @340kgs. with 20mm and down size graded granite metal coarse aggregates @0.7cum and fine aggregates @0.47cum with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 height upto 5 mtrs	Cum	5400.00	Rupees Five Thousand Four Hundred Only
11	5.30	Supplying, fitting and placing TMT bar reinforcement in sub-structure complete as per drawing and technical specifications complete as per specifications MORTH specification No. 1600 & 2200	MT	60000.00	Rupees Sixty Thousand Only

Srinivasa B.G
Contractor

28/8/19
Executive Engineer
SWD, R.R.Nagara Zone

Scanned by CamScanner

12	22.00	Providing Weep Holes in Brick Masonry / Plain / reinforced concrete abutment, wing wall / return wall with 100mm dia AC pipe, extending through the full width of the structure with slope of 1V-20H towards drawing foce. Complete as per drawing and technical specifications complete as per the specification and direction of the Engineer incharge	No.s	158.00	**Rupees One Hundred Fifty Eight Only**
13	575.00	Loading and unloading of earth, placing tipper at loading point, loading with from end loader, dumping, turning for return trip, including cost of Hauling and return trip complete as per specifications. Morth chapter-1. Carriage of excess earth from work spot to outer skert of the city. Collecting, Conveying and disposal of surplus/excavated earth to designated dumping site (15.0 kms) as directed by the engineer-in-	Cum	80.00	**Rupees Eighty Only**

Srinivasa B.h.
Contractor

28/8/19
Executive Engineer
SWD, R.R.Nagara Zone

Scanned by CamScanner